

Start Up Checklist

Remember "TAPS"

Thaw Float box Bottle of defoamer (or vegetable oil)	Sap pump is hooked up, thawed, primedSap filter is assembled, thawed
Auto Draw-off Confirm draw-off / safety settings Toggle draw-off to AUTO Toggle alarm to ON Toggle stack temp monitor to ON	Syrup probe is clean and properly installedAny other warning system(s) are ON
Pans All gaskets are in place Front pan is clean, free of niter	Check level in flue panCheck level in front pan
Sap Head tank is full Head tank valve is open, inspected	☐ Float box(es) have proper flow☐ OPEN TRANSFER VALVE
Light It Up! While you are boiling, set a timer so that Defoamer / vegetable oil	at you remember Fuel / stack temperature